NBS4MED

NBS4MED self-evaluation: summary report

Area	Assessment scale	Date
İzmir Green Roof Pilot, Türkiye	**Site / Project Area**	**2026-10-17**

Site context. Selected risks: Heatwaves; Flooding. Urban density: High. Public land available: Limited.

Criterion profile

Fixed 0 to 100% axis. Provisional levels. Unknown is never shown as zero.

Current NBS integration (C1)

C1 NBS Integration Status — **33%** · Partial, 2 / 6 points


Enabling and implementation conditions (C2 to C5)

C2 Policy & Planning — **33%** · Partial, 2 / 6 points

C3 Institutional & Technical Capacity — **Not rated: Unknown answers**, 2 of 3 indicators scored · 1 Unknown

C4 Stakeholder Engagement — **50%** · Partial, 2 / 4 points

C5 Funding & Sustainability — **17%** · Insufficient, 1 / 6 points



Provisional combined assessment score (secondary; not a validated measure of NBS integration): The overall percentage is not shown because 1 indicator is Unknown (3.3). Resolve it to see the overall score.

Completeness (14 indicators): 13 scored · 1 Unknown · 0 unanswered · 0 Not applicable

Confidence in the 13 scored answers (self-reported): documented evidence 0 · staff estimate 0 · informal judgement 0 · not stated 13. A complete answer is not necessarily documented evidence.

Major gaps and improvement actions

Provisional display order (score 0, then 1, then Unknown). Not a validated ranking.

1. **1.3 — Link to grey infrastructure** (Gap, Score 0): Introduce a step in infrastructure projects to consider NBS at the design stage.
2. **2.3 — Targets and monitoring** (Gap, Score 0): Define a small set of measurable NBS targets, for example area, number or condition of solutions, with a baseline year.
3. **5.2 — Long-term maintenance budget** (Gap, Score 0): Prepare an operation and maintenance budget and clarify who is responsible for funding it.

11 more findings are in the detailed report.

Key limitations. Matching covers heatwaves, flooding and drought only, with unvalidated weights. Costs are illustrative. Climate-risk mitigation impact is not currently estimated.

Preliminary NBS options

Provisional rule-based match to the selected risks. Not a validated ranking, feasibility check or predicted impact.

Relevant to the selected risks

Green roof Applicability: **Requires verification**	Heatwaves; Flooding
Green corridor Applicability: **Not yet checked**	Heatwaves; Flooding
Urban forest (Miyawaki method) Applicability: **Not yet checked**	Heatwaves; Flooding

Green roof (Green infrastructure, provisional): Heatwaves (moderately); Flooding (moderately). Uses existing roof space, not public land. Roof availability and structure still need checking. **Structural suitability of the roof requires assessment (assessment pending or Unknown). This option has High technical complexity.**

Green corridor (Green infrastructure, provisional): Heatwaves (strongly); Flooding (weakly). Land need fits the available public land.

Urban forest (Miyawaki method) (Green infrastructure · Ecosystem restoration, provisional): Heatwaves (strongly); Flooding (weakly). Land need exceeds the available public land, which lowers the provisional match. **This option has Medium technical complexity.**

Shared implementation conditions

- **5.1 Capital funding**: Score 1: Some funding is secured or likely, but it does not cover the planned NBS.
- **5.2 Long-term maintenance budget**: Score 0: No budget covers maintenance, watering or replacement of NBS.
- **3.2 Technical know-how**: Score 1: Some experience or guidance exists, but it is limited to certain NBS types or relies on outside support.

Supporting calculations and indicative cost

Green roof · Applicability: **Requires verification**

Inputs: Roof area to green **800** m^2 (Your value) · Design rainfall event depth **30** mm (Your value)

Roof structural suitability requires verification; figures assume the roof can carry the system.

Physical quantities and water volumes

Rain falling on the roof in this event	**24** m^3 Arithmetic on your inputs	Substrate volume to buy	**64** m^3 Arithmetic on your inputs

Climate-risk mitigation impact

Quantitative climate-risk mitigation impact is not currently estimated.

Literature reference evidence

Rainwater retained in this single event (scenario)	**6.43 – 14.8** m^3 (one event) Published reference

Literature-based event retention is an illustrative scenario, not a validated local forecast. It applies published results from other places to your roof. Source: G01 · UK experimental roofs, 2015 · S06

Cost (demo assumptions, EUR, not local prices)

Illustrative Scenario Cost — Not a Local Price Estimate

Construction cost (one-off)	**23,240 – 78,160** EUR (base 41,860) Demo assumption
Annual maintenance (per year)	**800 – 4,000** EUR (base 2,000) Demo assumption

Reference example (Hamburg, 2017; source S04): EUR 23,200 – 58,400 (median 35,200). Another place and year: not a current local price.

No price year: demo prices are not from a dated price list.